

15 May 2017

Wood Island Life Saving Station Bidding information

Questions from May 9 walkthrough:

Q: When cleaning cistern – Section 03133- how should cleaning chemicals be disposed?

A: Contractor is responsible for transportation of cleaners and residue to site of legal disposal.

Q: What is the scope of finish ceilings?

A: Except for Boat Room 109, all ceilings are to be plaster with prime paint coat. At Boat Room 109, contractor shall supply beadboard tongue and groove finish with prime paint coat.

Q: Are there provisions for contractor transportation to Wood Island?

A: Contractor is responsible.

Q: Is Bid Bond required?

A: Bid Bond is NOT required.

Materials and Services Bid Addendum 1:

1. Shingle Specifications

Revise

Length 18 inches and Thickness ½" at butt

To

Length 16 inches and Thickness 3/8" at butt

2. Door Schedule

Delete

Door 209 from bid

3. Boat Room Doors

Clarification

Contract bid includes structural framing of openings for Boat Room Doors

Repair Phase II Bid Addendum 1:

1. Section 04901 Masonry Restoration and Cleaning

Add

At two exterior chimneys, 1" thick bluestone cap set flush with top of exterior brick.

2. Section 06100 Rough Carpentry

Clarification

Structural framing of Window opening 1-07 and any other windows required is included in bid.

3. Door Schedule

Delete

Installation of Door 209 from bid

3. Drawing A-10/4

Revise the words "White Cedar" to "Asphalt"